



A DIVISION OF J.T. ADAMS CO., INC.

4520 WILLOW PARKWAY
CLEVELAND, OHIO 44125
PHONE (216) 641-3290
FAX (216) 641-1223
www.tensile.com

CERTIFIED TEST REPORT

Job No.: 2303-09-0561
Date: 4-6-2023
Cust. PO#: Verbal-Lance

Description: 4 Samples:
1 1/4" Dia. x 7" Long Threaded Screw/Collar
3' High House Jack
5' High House Jack
7' High House Jack

TEST RESULTS

Customer Reqs: Proof to 20,000 lbs

Description

Results

1 1/4" Threaded Screw/Collar	Proof loaded to 20,300 lbs; Held for 30 seconds Load Test: Failure occurred at 55,000 lbs, then screw started to bend. Threads did not strip; Stopped at 112,000 lbs.
3' High Tube/Plate	Proof loaded to 21,000, held for 30 seconds; no change in diameter or length.
5" High Tube/Plate	Proof loaded to 20,000 lbs; no change in diameter.
7' High Tube/Plate	Proof loaded to 20,000 lbs; no change in diameter.

The above **conforms** to requirements listed.

Tracey Waughman
Authorized Agent